

roof void ventilation

AIRTRAK™

**AIRTRAK-IL100**  
Inline Ventilator 100mm  
Supplied by Nicholson  
Tel 0845 0098 980  
Web www.nicholsonsts.com

**Material**  
0.7mm stainless steel, vinyl coated GRP insect mesh

**Ventilation**  
25mm continuous air gap equivalent


**Dimensions**  
OA girth 100mm, length 1000mm

**Compatibility**  
For use with lead and hard metal roofing on various ventilation details

**Installation**  
The IL100 is a flat profiled ventilator that can be fixed with non ferrous fixings to raking and straight edges to introduce a drip edge and ventilation. The ventilator can be mitred at corners and trimmed to length with a large pair of tin snips. Ensure that a minimum of 25mm airflow is achieved throughout the ventilation detail.

**To specify**  
Airtrak IL100 Inline Ventilator 100mm

**Also available**  
IL125 Inline Ventilator 125mm  
IL145 Inline Ventilator 145mm  
IL180 Inline Ventilator 180mm  
IL220 Inline Ventilator 220mm



© Nicholson 2015	<b>AIRTRAK-IL100</b> Inline Ventilator 100mm Supplied by Nicholson Tel 0845 0098 980 Web www.nicholsonsts.com	Revision Date	Description	Drawing Purpose: Construction detail			Drawing title <b>AIRTRAK-IL 100</b>	
Construction Risks				Drawn by	Checked by	Authorized by		
Maintenance / Cleaning risks							Scale@A3: 1:2	Drawing Number:
Demolition Adaptation Risks							Drawing Date 06th July 2015	Revision Date Revision