

roof void ventilation

AIRTRAK™

AIRTRAK-IL180

Inline Ventilator 180mm
Supplied by Nicholson
Tel 0845 0098 980
Web www.nicholsonsts.com

Material
0.7mm stainless steel, vinyl coated GRP insect mesh

Ventilation
25mm continuous air gap equivalent


Dimensions
OA girth 180mm, length 1000mm

Compatibility
For use with lead and hard metal roofing on various ventilation details

Installation
Where the roof covering is nailed to the layboard, the nail heads should be sealed using solder or lead burned dots. The IL180 is a flat profiled ventilator that can be fixed with non ferrous fixings to raking and straight edges to introduce a drip edge and ventilation. The ventilator can be mitred at corners and trimmed to length with a large pair of tin snips. Ensure that a minimum of 25mm airflow is achieved throughout the ventilation detail.

To specify
Airtrak IL180 Inline Ventilator 180mm

Also available
IL100 Inline Ventilator 100mm
IL125 Inline Ventilator 125mm
IL145 Inline Ventilator 145mm
IL220 Inline Ventilator 220mm



© Nicholson 2015	AIRTRAK-IL180 Inline Ventilator 180mm Supplied by Nicholson Tel 0845 0098 980 Web www.nicholsonsts.com	Revision Date	Description	Drawing Purpose: Construction detail			Drawing title AIRTRAK-IL180	
Construction Risks				Drawn by	Checked by	Authorized by		
Maintenance / Cleaning risks							Scale@A3: 1:2	Drawing Number:
Demolition Adaptation Risks							Drawing Date 25th Sep 2015	Revision Date Revision