

roof void ventilation

AIRTRAK™

AIRTRAK-IL145
Inline Ventilator 145mm
Supplied by Nicholson
Tel 0845 0098 980
Web www.nicholsonsts.com

Material
0.7mm stainless steel, vinyl coated GRP insect mesh

Ventilation
25mm continuous air gap equivalent


Dimensions
OA girth 145mm, length 1000mm

Compatibility
For use with lead and hard metal roofing on various ventilation details

Installation
The IL145 is a flat profiled ventilator that can be fixed with non ferrous fixings to raking and straight edges to introduce a drip edge and ventilation. The ventilator can be mitred at corners and trimmed to length with a large pair of tin snips. Ensure that a minimum of 25mm airflow is achieved throughout the ventilation detail.

To specify
Airtrak IL145 Inline Ventilator 145mm

Also available
IL100 Inline Ventilator 100mm
IL125 Inline Ventilator 125mm
IL180 Inline Ventilator 180mm
IL220 Inline Ventilator 220mm



| | | | | | | | | |
|------------------------------|--|---------------|-------------|---|------------|---------------|---------------------------------|------------------------|
| © Nicholson 2015 | AIRTRAK-IL145 Inline Ventilator 145mm Supplied by Nicholson Tel 0845 0098 980 Web www.nicholsonsts.com | Revision Date | Description | Drawing Purpose: Construction detail | | | Drawing title AIRTRAK-IL 145 | |
| Construction Risks | | | | Drawn by | Checked by | Authorized by | | |
| Maintenance / Cleaning risks | | | | | | | Scale@A3: 1:2 | Drawing Number: |
| Demolition Adaptation Risks | | | | | | | Drawing Date 25th Sep 2015 | Revision Date Revision |